



ADDENDUM

September 16, 2025

RE: CITY OF MOBILE BID #5997 FOR 33,000LB GVWR CREW CAB TRUCK WITH HYDRAULIC DUMPING CONTRACTOR BODY

Please consider this to be Addendum to City of Mobile Bid #5997 for 33,000lb GVWR Crew Cab Truck with Hydraulic Dumping Contractor Body.

The following are **additions** to the **Dumping Contractor Body specifications** and need to be **added to your bid package**. They had not been included when the bid package was issued.

Thank you for your consideration in this matter.


John Paine
Purchasing Agent
City of Mobile

JP/lw

HYDRAULIC DUMPING CONTRACTOR BED WITH FOLD DOWN OR DROP DOWN SIDES AND PINTLE TRAILER HITCH

HYDRAULIC DUMPING PRO-CONTRACTOR BED WITH FOLD DOWN OR DROP DOWN
SIDES.

12'DRW

1/8" DIAMOND PLATE STEEL FLOOR

3" CHANNEL CROSS MEMBERS

6" CHANNEL LONGBEAMS SET AT 34" WIDE

FULL LENGTH FOLD-DOWN SIDES & REAR GATE

3"x4" TUBE BULKHEAD W/STOP, TAIL,TURN & REVERSE LIGHTS

BUILD BULKHEAD TO FIT TRUCK

SINGLE 7-WAY TRAILER PLUG

LED LIGHTS

UNDERCOATED

POWDER COATED BLACK

GLOSS BLACK STEEL UNDERBODY TRUCK TOOL BOX W/ALUMINUM DOOR

18"x18"x48"

POWDER COATED DIAMOND TREAD ALUMINUM DOOR.

18x18 INCH WELDED BLACK STRUCTURAL STEEL MOUNTING BRACKETS

30 TON HEAVY DUTY SWIVEL TYPE PINTLE HOOK

ALLOWS TOWING HEAVY EQUIPMENT OVER UNEVEN TERRAIN

STRONG FORGED STEEL CONSTRUCTION

SPRING-LOADED PINTLE HOOK LOCK ARM PROVIDES A SECURE HOLD ONTO 3IN I.D

LUNETTE EYES AND DRAWBARS

HITCH TO BE RATED UP TO 60,000 LBS.

7-WAY TRAILER PLUG, TRUCK-SIDE

7-WAY ROUND

BUILT IN SAFETY LATCH FOR TRAILER P,LUG

SPRING-LOADED DOOR PROTECTS TERMINALS WHEN NOT IN USE.

PROVIDE VALVES, FITTINGS, HOSES, GLADHANDS TO INSTALL THE TRACTOR PACKAGE,
AND STEEL TO FABRICATE HITCH PLATE.

INSTALL CONTRACTOR BODY ON TRUCK

INSTALL HITCH PLATE AND PINTLE HITCH

PAINT ALL AREAS AFFECTED BY INSTALL

INSTALL TRACTOR / TRAILER PACKAGE ONTO TRUCK, ROUTE AIR LINES TO REAR OF
TRUCK, PLUMB AIR LINES, INSTALL GLADHANDS