

ADDENDUM 2

RE: City of Mobile Bid #6069 for Snowplows

September 10, 2026

Please consider the following to be Addendum 2 to City of Mobile Bid #6069 for SNOWPLOWES.

Plows will be mounted locally by others.

The Freightliner Chassis was ordered without the factory snowplow prep kit.

The plow shall be provided with an Electric Over Hydraulic Power System, as the truck was not ordered without an on-board hydraulic system for snowplow.

Attached is a list of items needed to mount and will be provided by the installer in Mobile.

Vendor to provide a Cheek Plate Mount for the snowplow.

The truck's frames are one (1) solid piece from the rear of the frame to the front bumper.

There is no bolted on or welded on piece to the frame or frame extension.

Attached are photos of the front of the truck(s) to which the plows will be mounted.

Thank you for your consideration in this matter.

Sincerely,

John Paine
Purchasing Agent
City of Mobile
JP/lw

WORK TO BE DONE TO MOUNT SNOWPLOW

- Provide black underbody toolbox with aluminum door to house electric/hydraulic power unit
- Remove front bumper
- Layout frame rails for plow mounting brackets
- Mag-drill frame rails
- Install brackets & quick hitch assembly
- Torque bolts & torque seal
- Layout frame rail for toolbox mounts
- Mount toolbox being used to house power unit
- Install electric/hydraulic power unit
- Route electrical cables from battery to power unit and from power unit to plow
- Build hydraulic hoses & fittings
- Route hydraulic lines from power unit to plow mount
- Secure cables and hydraulic lines to frame rails avoiding heat sources and abrasion points
- Route cables for in-cab controls
- Install plow
- Test system
- Vendor to provide any additional items not listed to mount snowplow to truck

IMAGE 1



IMAGE 2



IMAGE 3



IMAGE 4



IMAGE 5



IMAGE 6

